CERTIFICATE OF COMPLIANCE

No. C13C051

Holder of Certificate: GREE Electric Appliances Inc. of zhuhai
Jinji West Road, Qianshan, Zhuhai, Guangdong 519070, P. R. China
Product: Air Conditioner
Model/Type:

GKH18K3FI
GUHD18NK3FO

Is complied with:

EMC Directive: 2004/108/EC

Test acc. To: EN55014-1: 2006+A1:2009+A2:2011
EN55014-2: 1997+A1: 2001+A2:2008
EN61000-3-2: 2006+A1:2009+A2:2009
EN61000-3-3: 2008

Report Number: GER13C051E

This certificate of conformity is based on the adequate technical documentation and the tests in Testing Laboratory of Gree Electric Appliances Inc. of Zhuhai. This declaration becomes invalid if technical or operational modifications are introduced without the manufacturer's consent.
Note: Testing Laboratory of Gree Electric Appliances Inc. of Zhuhai is accredited by TUV Rheinland, CNAS, VDE, etc.

(Authorized signature)
Name: Li zhikun
Date: 2013-03-08

Jinji West Road, Qianshan, Zhuhai, Guangdong 519070 P.R.China
Tel:+86 756 8614883; Fax:+86 756 8614998

EMC TEST REPORT

Product Name	:	Split-type Room Air Conditioner
Product Model	:	GKH18K3FI(indoor unit) GUHD18NK3FO(outdoor unit)
Serial No.	:	Pre-production model
Date of Receipt	:	2013.03.08
Test Period	:	2013.03.08
Applicant	:	Gree Electric Appliances, Inc. of Zhuhai
Testing Location	:	Gree EMC Testing Lab.

Applicable The Following Selected Harmonized Standards:

EN55014-1: 2006+A1:2009+A2:2011
EN55014-2: 1997+A1: 2001+A2:2008
EN61000-3-2: 2006+A1:2009+A2:2009
EN61000-3-3: 2008

Tested by	:	Liujie		2013-03-08
		Printed Name	*Signature*	*Date((YY-MM-DD)*
Reviewed by	:	Li zhikun		2013-03-08
		Printed Name	*Signature*	*Date((YY-MM-DD)*

EMC LABORATORY OF GREE ELETRIC APPLIANCES INC. OF ZHUHAI

Address: Jinji West Road. Qianshan Zhuhai China Postcode: 519070
Tel:（0756）8668624 Fax:（0756）8614998

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

Contents

CONTENTS		**2**
1.	**TEST SUMMARY**	**3**
2.	**PRODUCTS DESCRIPTION**	**4**
3.	**LIST OF TEST AND MEASUREMENT INSTRUMENTS**	**5**
4.	**EMISSION TEST**	**6**
4.1	Main and Additional Terminal Continuous Disturbance Voltage	6
4.2	Discontinuous Interference on AC Mains	17
4.3	Disturbance Power	19
4.4	Harmonics on AC Mains	25
4.5	Voltage Fluctuation on AC Mains	29
5.	**IMMUNITY TESTS**	**30**
5.1	Electrostatic Discharge (ESD)	30
5.2	Electrical Fast Transient/Burst (EFT)	32
5.3	Surge	33
5.4	Immunity to conducted Disturbances, induced by RF fields	34
5.5	Voltage Dips and Short interruptions	35

Remark:

Principle of Configuration Selection of test set-up and operation mode

Emission: The Equipment under test (EUT) was configured to measure its highest possible radiation level. The test modes were adapted accordingly in reference to the instructions for use.

Immunity: The equipment under test (EUT) was configured to have its highest possible susceptibility against the tested phenomena. The test modes were adapted accordingly in reference to the instructions for use.

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

1. Test Summary

4. EMISSION TESTS:

4.1 Mains and additional Terminal Continuous Disturbance Voltage

Test Result: Pass

4.2 Discontinuous Interference on AC Mains

Test Result: Pass

4.3 Disturbance Power

Test Result: Pass

4.4 Harmonics on AC Mains

Test Result: Pass

4.5 Voltage Fluctuation on AC Mains

Test Result: Pass

5. IMMUNITY TESTS:

5.1 Electrostatic Discharge (ESD)

Test Result: Pass

5.2 Electrical Fast Transient/Burst (EFT)

Test Result: Pass

5.3 Surge

Test Result: Pass

5.4 Immunity to conducted Disturbances, induced by RF fields

Test Result: Pass

5.5 Voltage Dips and Short interruptions

Test Result: Pass

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

2. Products Description

Power Supply	:	220-240V 1N~ 50Hz
Power Cord	:	Unshielded
Interconnection Line	:	Unshielded
Additional Equipment	:	IR Remote Controller
Protection	:	Class Ⅰ
Operation Mode	:	Standby Fan Cool Heat Dry Auto
General Description	:	

About the particular information of the modes, please refer to Technical Construction Document, user manual, etc.

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

3. List of Test and Measurement Instruments

Equipment	Manufacturer	Model No.	Serial No.	Calibrated until
EMI Test Receiver	R&S	ESCS30	100353	07/07/2013
L.I.S.N	R&S	ENV4200	100031	07/07/2013
Pulse limiter	R&S	ESH3-Z2	100066	07/07/2013
Absorbing Clamp	R&S	MDS-21	100194	07/07/2013
Voltage Probe	Schwarbeck	TK9420	9426-235	07/07/2013
Clicks Analyzer	Schaffner	DIA1512D	21534	07/07/2013
Harmonic/Flicker Testing system	CI	PACS-3	72823	03/23/2013
ESD Simulator System	TESTQ	NSG438	1198	08/13/2013
EFT/B Generator	Schaffner	NSG2025-4	1237	07/07/2013
Capacitive Coupling Clamp	Schaffner	CDN126	532	07/07/2013
RF-Generator	Schaffner	NSG2070	1022	07/07/2013
Coupling/Decoupling Network	Schaffner	CDN M316	15072	07/07/2013
EM clamp	Schaffner	KEMZ801	15792	07/07/2013
Voltage Swell/DIP/Interrupt Source	KeyTek ECAT	EP62	0512181	11/30/2013
Surge Generator-Combination Wave	KeyTek ECAT	510A	0512182	11/30/2013
Coupling/Decoupling Network	KeyTek ECAT	E4554A	0512183	11/30/2013

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

4. Emission Test

4.1 Main and Additional Terminal Continuous Disturbance Voltage

Date of testing	:	2013.03.08
Temperature	:	26°C/18°C
Operational mode	:	Cool /Heat, High speed
Humidity	:	65%RH~67%RH
Test procedure	:	EN55014-1: 2006+A1:2009+A2:2011
Frequency range	:	0.15M - 30MHz
Kind of test site	:	Shielded room
Test result	:	Pass

1.Test Setup:

The EUT is on an insulating plane (height=80cm)
The distance between EUT and L.I.S.N is 80cm.
The distance between EUT and other metal conductors grounded is at least 80cm.

2.If the result of the measurement with the Quasi Peak detector is below the Average limit, the measurement with Average Detector has been omitted.
Disturbances other than those mentioned are small or not detectable.

Receiver setup:
Detector:Peak+Average; IF-BW: 9kHz; Step: 4.5kHz; M-Time: 20ms
The test data are as follows:

At main terminal: Pass

Model: GKH18K3FI(indoor unit)

Cooling mode **Port: Power Cord- L line**

Final measurement results

EDIT PEAK LIST (Final Measurement Results)				
Trace1:	14-QP			
Trace2:	14-AV			
Trace3:	---			
TRACE	FREQUENCY	LEVEL dBµV		DELTA LIMIT dB
1 Quasi Peak	342 kHz	39.24	L1 gnd	-19.91
2 Average	342 kHz	35.35	L1 gnd	-14.74
1 Quasi Peak	458 kHz	42.68	L1 gnd	-14.04
2 Average	458 kHz	40.17	L1 gnd	-6.77
2 Average	1.142 MHz	32.73	L1 gnd	-13.27
1 Quasi Peak	1.23 MHz	36.94	L1 gnd	-19.05
1 Quasi Peak	4.734 MHz	46.05	L1 gnd	-9.94
2 Average	4.738 MHz	40.40	L1 gnd	-5.59
2 Average	5.282 MHz	39.92	L1 gnd	-10.07
1 Quasi Peak	5.306 MHz	45.75	L1 gnd	-14.24
2 Average	21.106 MHz	28.22	L1 gnd	-21.77
1 Quasi Peak	21.198 MHz	34.35	L1 gnd	-25.64

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

Model: GKH18K3FI(indoor unit)

Cooling mode **Port: Power Cord- N line**

Final measurement results

EDIT PEAK LIST (Final Measurement Results)					
Trace1:	14-QP				
Trace2:	14-AV				
Trace3:	---				
TRACE		FREQUENCY	LEVEL dBµV		DELTA LIMIT dB
1	Quasi Peak	342 kHz	40.03	L1 gnd	-19.12
2	Average	342 kHz	35.50	L1 gnd	-14.59
2	Average	454 kHz	40.10	L1 gnd	-6.94
1	Quasi Peak	462 kHz	40.22	L1 gnd	-16.43
2	Average	970 kHz	32.50	L1 gnd	-13.49
1	Quasi Peak	1.846 MHz	34.81	L1 gnd	-21.18
1	Quasi Peak	4.698 MHz	45.11	L1 gnd	-10.88
2	Average	4.706 MHz	40.95	L1 gnd	-5.04
1	Quasi Peak	5.214 MHz	45.36	L1 gnd	-14.64
2	Average	5.214 MHz	40.23	L1 gnd	-9.76
2	Average	21.022 MHz	28.21	L1 gnd	-21.79
1	Quasi Peak	21.25 MHz	34.02	L1 gnd	-25.97

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

Model: GKH18K3FI(indoor unit)

Heating mode **Port: Power Cord- L line**

Final measurement results

EDIT PEAK LIST (Final Measurement Results)				
Trace1:	14-QP			
Trace2:	14-AV			
Trace3:	---			
TRACE	FREQUENCY	LEVEL dBµV		DELTA LIMIT dB
1 Quasi Peak	342 kHz	38.94	L1 gnd	-20.20
2 Average	342 kHz	34.87	L1 gnd	-15.23
1 Quasi Peak	458 kHz	42.20	L1 gnd	-14.52
2 Average	458 kHz	39.75	L1 gnd	-7.19
2 Average	998 kHz	32.93	L1 gnd	-13.06
1 Quasi Peak	1.814 MHz	33.89	L1 gnd	-22.10
2 Average	4.738 MHz	40.12	L1 gnd	-5.87
1 Quasi Peak	4.746 MHz	44.03	L1 gnd	-11.96
2 Average	5.218 MHz	40.46	L1 gnd	-9.53
1 Quasi Peak	5.222 MHz	45.18	L1 gnd	-14.81
1 Quasi Peak	20.934 MHz	36.23	L1 gnd	-23.76
2 Average	21.186 MHz	31.01	L1 gnd	-18.98

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

Model: GKH18K3FI(indoor unit)

Heating mode **Port: Power Cord- N line**

Final measurement results

EDIT PEAK LIST (Final Measurement Results)					
Trace1:	14-QP				
Trace2:	14-AV				
Trace3:	---				
TRACE		FREQUENCY	LEVEL dBµV		DELTA LIMIT dB
1	Quasi Peak	342 kHz	39.47	L1 gnd	-19.67
2	Average	342 kHz	34.98	L1 gnd	-15.11
2	Average	458 kHz	39.50	L1 gnd	-7.43
1	Quasi Peak	462 kHz	39.68	L1 gnd	-16.97
2	Average	970 kHz	32.42	L1 gnd	-13.57
1	Quasi Peak	1.794 MHz	37.13	L1 gnd	-18.87
1	Quasi Peak	4.718 MHz	43.84	L1 gnd	-12.15
2	Average	4.762 MHz	40.32	L1 gnd	-5.67
1	Quasi Peak	5.274 MHz	46.33	L1 gnd	-13.66
2	Average	5.274 MHz	40.73	L1 gnd	-9.26
1	Quasi Peak	20.898 MHz	36.81	L1 gnd	-23.19
2	Average	20.99 MHz	31.37	L1 gnd	-18.62

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

Model: GUHD18NK3FO(outdoor unit)

Cooling mode **Port: Power Cord- L line**

EDIT PEAK LIST (Final Measurement Results)				
Trace1:	14-QP			
Trace2:	14-AV			
Trace3:	---			
TRACE	FREQUENCY	LEVEL dBµV		DELTA LIMIT dB
1 Quasi Peak	162 kHz	52.87	L1 gnd	-12.49
2 Average	182 kHz	47.68	L1 gnd	-9.22
2 Average	422 kHz	29.55	L1 gnd	-18.27
1 Quasi Peak	562 kHz	31.48	L1 gnd	-24.51
2 Average	1.362 MHz	31.24	L1 gnd	-14.75
1 Quasi Peak	1.386 MHz	38.41	L1 gnd	-17.58
1 Quasi Peak	3.49 MHz	43.19	L1 gnd	-12.80
2 Average	4.314 MHz	39.12	L1 gnd	-6.88
1 Quasi Peak	11.358 MHz	43.99	L1 gnd	-16.00
2 Average	12.402 MHz	38.32	L1 gnd	-11.67
2 Average	12.646 MHz	40.14	L1 gnd	-9.85
1 Quasi Peak	12.678 MHz	44.56	L1 gnd	-15.43

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

Model: GUHD18NK3FO(outdoor unit)

Cooling mode **Port: Power Cord- N line**

EDIT PEAK LIST (Final Measurement Results)				
Trace1:	14-QP			
Trace2:	14-AV			
Trace3:	---			
TRACE	FREQUENCY	LEVEL dBµV		DELTA LIMIT dB
1 Quasi Peak	162 kHz	48.81	L1 gnd	-16.54
2 Average	342 kHz	34.80	L1 gnd	-15.29
1 Quasi Peak	502 kHz	36.45	L1 gnd	-19.54
2 Average	502 kHz	31.36	L1 gnd	-14.63
1 Quasi Peak	1.426 MHz	41.92	L1 gnd	-14.07
2 Average	1.826 MHz	36.69	L1 gnd	-9.30
1 Quasi Peak	4.37 MHz	46.96	L1 gnd	-9.03
2 Average	4.454 MHz	41.88	L1 gnd	-4.12
2 Average	5.246 MHz	40.88	L1 gnd	-9.12
1 Quasi Peak	11.27 MHz	42.79	L1 gnd	-17.20
1 Quasi Peak	12.974 MHz	46.01	L1 gnd	-13.99
2 Average	13.482 MHz	38.06	L1 gnd	-11.93

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

Model: GUHD18NK3FO（outdoor unit）

Heating mode **Port: Power Cord- L line**

EDIT PEAK LIST (Final Measurement Results)				
Trace1:	14-QP			
Trace2:	14-AV			
Trace3:	---			
TRACE	FREQUENCY	LEVEL dBµV		DELTA LIMIT dB
1 Quasi Peak	162 kHz	53.53	L1 gnd	-11.82
2 Average	182 kHz	48.47	L1 gnd	-8.43
2 Average	402 kHz	30.85	L1 gnd	-17.49
1 Quasi Peak	506 kHz	30.34	L1 gnd	-25.65
1 Quasi Peak	1.386 MHz	38.33	L1 gnd	-17.66
2 Average	1.806 MHz	32.35	L1 gnd	-13.64
1 Quasi Peak	3.514 MHz	43.11	L1 gnd	-12.88
2 Average	4.314 MHz	38.66	L1 gnd	-7.33
2 Average	7.578 MHz	39.08	L1 gnd	-10.91
1 Quasi Peak	11.214 MHz	45.20	L1 gnd	-14.79
1 Quasi Peak	13.282 MHz	47.71	L1 gnd	-12.28
2 Average	13.358 MHz	42.77	L1 gnd	-7.22

Model: GUHD18NK3FO（outdoor unit）

Heating mode **Port: Power Cord- N line**

EDIT PEAK LIST (Final Measurement Results)			
Trace1:	14-QP		
Trace2:	14-AV		
Trace3:	---		
TRACE	FREQUENCY	LEVEL dBµV	DELTA LIMIT dB
1 Quasi Peak	182 kHz	45.22 L1 gnd	-19.16
2 Average	342 kHz	34.92 L1 gnd	-15.17
2 Average	482 kHz	32.05 L1 gnd	-14.34
1 Quasi Peak	622 kHz	36.13 L1 gnd	-19.86
1 Quasi Peak	1.806 MHz	41.91 L1 gnd	-14.08
2 Average	1.986 MHz	36.19 L1 gnd	-9.80
1 Quasi Peak	4.214 MHz	46.10 L1 gnd	-9.89
2 Average	4.414 MHz	40.97 L1 gnd	-5.02
2 Average	5.174 MHz	40.55 L1 gnd	-9.44
1 Quasi Peak	11.542 MHz	43.26 L1 gnd	-16.73
1 Quasi Peak	13.086 MHz	46.99 L1 gnd	-13.00
2 Average	13.246 MHz	41.65 L1 gnd	-8.34

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

According to EN55014.1, for terminal disturbance voltage, the test start frequency shall be obtained per the formula: f_{start}=60/L (MHz), so, here, the f_{start}=60/8.0 =7.5 MHz. Where, the length of interconnection line is 8.0 meters.

Model: GKH18K3FI(indoor unit)/GUHD18NK3FO(outdoor unit)

Cooling mode **Port:** Interconnection line at indoor unit

Cooling mode **Port:** Interconnection line at outdoor unit

Remark: The all margin values>10dB

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

Model: GKH18K3FI(indoor unit)/GUHD18NK3FO(outdoor unit)

Heating mode **Port: Interconnection line at indoor unit**

Heating mode **Port: Interconnection line at outdoor unit**

Remark: The all margin values>10dB

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

4.2 Discontinuous Interference on AC Mains

Date of testing	:	2013.03.08
Temperature	:	24°C~28°C
Humidity	:	66%RH~67%RH
Test procedure	:	EN55014-1: 2006+A1:2009+A2:2011
Frequency range	:	0.15M – 30MHz
Kind of test site	:	Shielded room
Operational mode	:	Dry
Test result	:	Pass

1.Test Setup

The EUT is on an insulating plane (height=80cm)
The distance between EUT and L.I.S.N is 80cm.
The distance between EUT and other metal conductors grounded is at least 80cm.

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

2. Test results.

Model: GUHD18NK3FO（outdoor unit）					
Run A (Observation time=120Mins0Sec)					
Frequency (MHz)		0.15	0.5	1.4	30
Limit value (L)(**dB**μV)		66	56	56	60
Amount of clicks >L	Short (n1)	3	2	1	0
	Long (n2)	0	0	0	0
Total (n=n1+n2)		3	2	1	0
Click Rate (N=n/T)		0.03	0.02	0.01	0.00
Continuous(s)		0	0	0	0
Switching operations		---			
f factor		N/A			
Result		PASS			

Model: GKH18K3FI(indoor unit)					
Run A (Observation time=120Mins0Sec)					
Frequency (MHz)		0.15	0.5	1.4	30
Limit value (L)(**dB**μV)		66	56	56	60
Amount of clicks >L	Short (n1)	32	24	11	0
	Long (n2)	0	0	0	0
Total (n=n1+n2)		32	24	11	0
Click Rate (N=n/T)		0.28	0. 20	0. 09	0. 00
Continuous(s)		0	0	0	0
Switching operations		---			
f factor		N/A			
Result		PASS			

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

4.3 Disturbance Power

Date of testing	:	2013.03.08
Temperature	:	25°C/19°C
Operational mode	:	Cool /Heat, High speed
Humidity	:	65%RH~67%RH
Test procedure	:	EN55014-1: 2006+A1:2009+A2:2011
Frequency range	:	30M - 300MHz
Kind of test site	:	Shielded room
Test ports	:	AC Mains/ Interconnection line
Test result	:	Pass

1.Test Setup:

EUT and absorbing clamp are placed on an insulating plane (height=80cm). The distance between the absorbing clamp and other metal conductors grounded is 40cm above. EUT is connected to A.C power through an extended cord(≧6m). The absorbing clamp clamps the power line and moves along the power line to measure the maximum disturbance power emitted from the line. If EUT has an indoors unit and an outdoors unit, its interconnection lines and signal lines(or controlling lines) should be also measured ,too.

2.If the result of the measurement with the Quasi Peak detector is below the Average limit, the measurement with Average Detector has been omitted.

The power cord and interconnection line had been extended to a length of 6m and routed through an absorbing clamp. The clamp was moved along the cable to find the maximal emission.

Disturbances other than those mentioned are small or not detectable.

Receiver setup:

Detector:Peak+Average, IF-BW: 120kHz, Step: 60kHz, M-Time: 10ms.

The frequency spectra are as follows:

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

Model: GUHD18NK3FO（outdoor unit）

Cooling mode **Port: Power Cord**

Heating mode **Port: Power Cord**

Remark: The all margin values>10dB

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

Model: GKH18K3FI(indoor unit)/GUHD18NK3FO(outdoor unit)

Cooling mode **Port: Interconnection line, at indoor unit.**

Heating mode **Port: Interconnection line, at indoor unit.**

Remark: The all margin values>10dB

Model: GKH18K3FI(indoor unit)/GUHD18NK3FO(outdoor unit)

Cooling mode **Port: Interconnection line, at outdoor unit.**

Heating mode **Port: Interconnection line, at outdoor unit.**

Remark: The all margin values>10dB

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

Model: GKH18K3FI(indoor unit)

Cooling mode **Port: Power Cord**

EDIT PEAK LIST (Final Measurement Results)			
Trace1:	P14-QP		
Trace2:	P14-AV		
Trace3:	---		
TRACE	FREQUENCY	LEVEL dBpW	DELTA LIMIT dB
2 Average	34 MHz	23.39	-11.75
1 Quasi Peak	34.12 MHz	37.49	-7.66
1 Quasi Peak	52.48 MHz	25.90	-19.92
1 Quasi Peak	67.08 MHz	28.12	-18.25
1 Quasi Peak	88.72 MHz	30.64	-16.53
1 Quasi Peak	122 MHz	24.95	-23.45
1 Quasi Peak	157.72 MHz	21.52	-28.20

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

Model: GKH18K3FI(indoor unit)

Heating mode **Port: Power Cord**

EDIT PEAK LIST (Final Measurement Results)			
Trace1:	P14-QP		
Trace2:	P14-AV		
Trace3:	---		
TRACE	FREQUENCY	LEVEL dBpW	DELTA LIMIT dB
2 Average	34.68 MHz	24.58	-10.58
1 Quasi Peak	37.64 MHz	35.13	-10.15
1 Quasi Peak	56.56 MHz	31.86	-14.12
1 Quasi Peak	83.44 MHz	25.89	-21.08
1 Quasi Peak	86.28 MHz	29.69	-17.38
1 Quasi Peak	119.64 MHz	32.32	-15.99
1 Quasi Peak	121.48 MHz	34.68	-13.69
2 Average	121.48 MHz	18.96	-19.42
1 Quasi Peak	164.44 MHz	22.80	-27.17
1 Quasi Peak	174 MHz	22.63	-27.69

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

4.4 Harmonics on AC Mains

Date of testing	:	2013.03.08
Temperature	:	25°C/18°C
Humidity	:	66%RH~67%RH
Test procedure	:	EN61000-3-2: 2006+A1:2009+A2:2009
Harmonics order	:	2 – 40
Equipment Class	:	A
Operational mode	:	Cool /Heat, High speed
Test result	:	Pass

1.Test Setup:

2. Test result.

The test results are shown as follows:

.

Model: GUHD18NK3FO（outdoor unit）

Cooling mode

THC(A): 0.80 I-THD(%): 7.89 POHC(A): 0.136 POHC Limit(A): 0.251

Highest parameter values during test:

V_RMS (Volts):	230.04	Frequency(Hz):	50.00
I_Peak (Amps):	17.792	I_RMS (Amps):	10.350
I_Fund (Amps):	10.310	Crest Factor:	1.733
Power (Watts):	2366.1	Power Factor:	0.995

Harm#	Harms(avg)	100%Limit	%of Limit	Harms(max)	150%Limit	%of Limit	Status
2	0.028	1.080	2.6	0.036	1.620	2.24	Pass
3	0.402	2.300	17.5	0.417	3.450	12.10	Pass
4	0.030	0.430	6.9	0.038	0.645	5.83	Pass
5	0.298	1.140	26.1	0.313	1.710	18.28	Pass
6	0.047	0.300	15.6	0.104	0.450	23.04	Pass
7	0.373	0.770	48.5	0.387	1.155	33.55	Pass
8	0.076	0.230	33.0	0.235	0.345	68.04	Pass
9	0.383	0.400	95.8	0.399	0.600	66.53	Pass
10	0.076	0.184	41.2	0.224	0.276	81.25	Pass
11	0.202	0.330	61.3	0.211	0.495	42.66	Pass
12	0.041	0.153	27.0	0.115	0.230	50.17	Pass
13	0.121	0.210	57.8	0.130	0.315	41.18	Pass
14	0.018	0.131	13.5	0.023	0.197	11.47	Pass
15	0.078	0.150	51.9	0.083	0.225	36.83	Pass
16	0.013	0.115	11.5	0.017	0.173	10.04	Pass
17	0.071	0.132	53.7	0.075	0.199	37.92	Pass
18	0.012	0.102	11.9	0.016	0.153	10.68	Pass
19	0.073	0.118	61.3	0.076	0.178	42.84	Pass
20	0.011	0.092	12.1	0.014	0.138	9.83	Pass
21	0.045	0.107	41.7	0.046	0.161	28.85	Pass
22	0.009	0.084	10.7	0.012	0.125	9.71	Pass
23	0.058	0.098	59.8	0.061	0.147	41.43	Pass
24	0.007	0.077	9.6	0.009	0.115	8.13	Pass
25	0.016	0.090	18.2	0.017	0.135	12.86	Pass
26	0.005	0.071	7.5	0.007	0.106	6.57	Pass
27	0.050	0.083	59.8	0.051	0.125	40.93	Pass
28	0.005	0.066	7.8	0.007	0.099	7.21	Pass
29	0.050	0.078	64.5	0.052	0.116	44.65	Pass
30	0.005	0.061	7.6	0.006	0.092	6.76	Pass
31	0.047	0.073	65.2	0.049	0.109	44.68	Pass
32	0.006	0.058	10.6	0.008	0.086	9.27	Pass
33	0.050	0.068	73.1	0.052	0.102	50.65	Pass
34	0.006	0.054	11.3	0.007	0.081	9.08	Pass
35	0.020	0.064	31.8	0.021	0.096	22.35	Pass
36	0.006	0.051	11.6	0.008	0.077	10.19	Pass
37	0.040	0.061	66.5	0.043	0.091	47.38	Pass
38	0.006	0.048	12.2	0.007	0.073	10.01	Pass
39	0.032	0.058	56.0	0.035	0.087	40.15	Pass
40	0.005	0.046	12.3	0.007	0.069	9.56	Pass

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

Model: GUHD18NK3FO（outdoor unit）

Heating mode

Test Result: Pass **Source qualification: Normal**
THC(A): 0.81 **I-THD(%): 8.11** **POHC(A): 0.134** **POHC Limit(A): 0.251**
Highest parameter values during test:

V_RMS (Volts):	230.03	Frequency(Hz):	50.00
I_Peak (Amps):	18.130	I_RMS (Amps):	10.677
I_Fund (Amps):	10.617	Crest Factor:	1.764
Power (Watts):	2437.2	Power Factor:	0.995

Harm#	Harms(avg)	100%Limit	%of Limit	Harms(max)	150%Limit	%of Limit	Status
2	0.024	1.080	2.3	0.034	1.620	2.09	Pass
3	0.399	2.300	17.3	0.419	3.450	12.15	Pass
4	0.024	0.430	5.6	0.032	0.645	4.95	Pass
5	0.298	1.140	26.1	0.310	1.710	18.13	Pass
6	0.047	0.300	15.8	0.067	0.450	15.00	Pass
7	0.385	0.770	50.1	0.397	1.155	34.39	Pass
8	0.037	0.230	16.1	0.065	0.345	18.76	Pass
9	0.394	0.400	98.4	0.408	0.600	67.93	Pass
10	0.059	0.184	31.8	0.086	0.276	31.29	Pass
11	0.207	0.330	62.6	0.213	0.495	43.09	Pass
12	0.021	0.153	13.9	0.039	0.230	17.10	Pass
13	0.120	0.210	57.2	0.129	0.315	40.84	Pass
14	0.016	0.131	11.9	0.020	0.197	10.18	Pass
15	0.077	0.150	51.2	0.082	0.225	36.46	Pass
16	0.012	0.115	10.4	0.016	0.173	9.04	Pass
17	0.070	0.132	53.1	0.075	0.199	37.84	Pass
18	0.010	0.102	9.7	0.013	0.153	8.33	Pass
19	0.073	0.118	61.4	0.076	0.178	42.73	Pass
20	0.010	0.092	10.6	0.012	0.138	9.03	Pass
21	0.044	0.107	41.5	0.047	0.161	29.44	Pass
22	0.007	0.084	8.7	0.010	0.125	7.75	Pass
23	0.059	0.098	60.2	0.061	0.147	41.21	Pass
24	0.008	0.077	10.0	0.010	0.115	8.67	Pass
25	0.016	0.090	17.4	0.018	0.135	13.50	Pass
26	0.005	0.071	7.5	0.007	0.106	6.38	Pass
27	0.050	0.083	59.7	0.052	0.125	41.64	Pass
28	0.005	0.066	9.2	0.008	0.099	7.63	Pass
29	0.050	0.078	63.8	0.051	0.116	44.07	Pass
30	0.005	0.061	8.7	0.007	0.092	7.58	Pass
31	0.047	0.073	64.6	0.050	0.109	45.78	Pass
32	0.006	0.058	10.8	0.008	0.086	9.22	Pass
33	0.049	0.068	71.3	0.052	0.102	51.33	Pass
34	0.006	0.054	11.7	0.009	0.081	10.73	Pass
35	0.019	0.064	30.2	0.021	0.096	22.24	Pass
36	0.006	0.051	11.4	0.007	0.077	9.40	Pass
37	0.038	0.061	62.0	0.047	0.091	52.03	Pass
38	0.005	0.048	10.5	0.007	0.073	9.80	Pass
39	0.030	0.058	52.5	0.038	0.087	43.15	Pass
40	0.005	0.046	11.4	0.008	0.069	11.69	Pass

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

Model: GKH18K3FI(indoor unit)

fan mode

Test Result: Pass **Source qualification: Normal**
THC(A): 0.16 **I-THD(pk%): 14.50** **POHC(A): 0.001** **POHC Limit(A): 0.251**
Highest parameter values during test:

V_RMS (Volts):	230.01	Frequency(Hz):	50.00
I_Peak (Amps):	1.106	I_RMS (Amps):	0.224
I_Fund (Amps):	0.211	Crest Factor:	1.818
Power (Watts):	51	Power Factor:	0.990

Harm#	Harms(avg)	100%Limit	%of Limit	Harms(max)	150%Limit	%of Limit	Status
2	0.096	1.080	8.9	0.099	1.620	6.09	Pass
3	0.120	2.300	5.2	0.122	3.450	3.53	Pass
4	0.012	0.430	2.9	0.013	0.645	2.03	Pass
5	0.023	1.140	2.0	0.023	1.710	1.37	Pass
6	0.001	0.300	0.5	0.002	0.450	0.39	Pass
7	0.002	0.770	0.2	0.002	1.155	0.17	Pass
8	0.001	0.230	0.4	0.001	0.345	0.30	Pass
9	0.001	0.400	0.2	0.001	0.600	0.17	Pass
10	0.001	0.184	0.3	0.001	0.276	0.22	Pass
11	0.001	0.330	0.4	0.001	0.495	0.27	Pass
12	0.001	0.153	0.4	0.001	0.230	0.32	Pass
13	0.001	0.210	0.3	0.001	0.315	0.26	Pass
14	0.000	0.131	0.2	0.000	0.197	0.14	Pass
15	0.000	0.150	0.2	0.000	0.225	0.19	Pass
16	0.000	0.115	0.3	0.000	0.173	0.21	Pass
17	0.000	0.132	0.2	0.000	0.199	0.20	Pass
18	0.000	0.102	0.3	0.000	0.153	0.25	Pass
19	0.000	0.118	0.2	0.000	0.178	0.18	Pass
20	0.000	0.092	0.2	0.000	0.138	0.21	Pass
21	0.000	0.107	0.2	0.000	0.161	0.20	Pass
22	0.000	0.084	0.3	0.000	0.125	0.27	Pass
23	0.000	0.098	0.2	0.000	0.147	0.22	Pass
24	0.000	0.077	0.3	0.000	0.115	0.27	Pass
25	0.000	0.090	0.2	0.000	0.135	0.27	Pass
26	0.000	0.071	0.3	0.000	0.106	0.23	Pass
27	0.000	0.083	0.2	0.000	0.125	0.20	Pass
28	0.000	0.066	0.3	0.000	0.099	0.22	Pass
29	0.000	0.078	0.2	0.000	0.116	0.20	Pass
30	0.000	0.061	0.3	0.000	0.092	0.26	Pass
31	0.000	0.073	0.2	0.000	0.109	0.20	Pass
32	0.000	0.058	0.2	0.000	0.086	0.22	Pass
33	0.000	0.068	0.2	0.000	0.102	0.17	Pass
34	0.000	0.054	0.3	0.000	0.081	0.26	Pass
35	0.000	0.064	0.2	0.000	0.096	0.23	Pass
36	0.000	0.051	0.3	0.000	0.077	0.26	Pass
37	0.000	0.061	0.2	0.000	0.091	0.20	Pass
38	0.000	0.048	0.2	0.000	0.073	0.21	Pass
39	0.000	0.058	0.2	0.000	0.087	0.22	Pass
40	0.000	0.046	0.3	0.000	0.069	0.30	Pass

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

4.5 Voltage Fluctuation on AC Mains

Date of testing	:	2013.03.08
Temperature	:	25°C
Humidity	:	66%RH
Test procedure	:	EN61000-3-3: 2008
Frequency Range	:	0-2kHz
Test observation period	:	120min
Operational mode	:	Dry
Test result	:	Pass

1.Test Setup:

2. Test result.

Remark:

Model	d_c [%]	d_{max} [%]	d (t)[ms]	Pst	Plt
GUHD18NK3FO（outdoor unit）	0.95	0.98	0.0	0.184	0.153
GKH18K3FI(indoor unit)	1.12	1.50	0.0	0.204	0.201
Limit	**3.30**	**6.00**	**500.0**	**1.000**	**0.650**

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

5. Immunity Tests

5.1 Electrostatic Discharge (ESD)

Date of testing	:	2013.03.08
Temperature	:	26°C~28°C
Humidity	:	55%RH
Test procedure	:	EN55014-2: 1997+A1: 2001+A2:2008
Basic Standard	:	IEC 61000-4-2:2008
Performance Criterion	:	B
Operational mode	:	Cool, High fan
Test result	:	Pass

1. Test setup

Note: HCP means Horizontal Coupling Plane,
VCP means Vertical Coupling Plane
GRP means Ground Reference Plane

The EUT was put on a 0.8m high wooden tabel/0.1m high for floor standing equipment standing on the ground reference plane(GRP) 3m by 2m in size, made by iron 1.0 mm thick.
A horizontal coupling plane(HCP) 1.6m by 0.8m in size was placed on the table, and the EUT with its cables were isolated from the HCP by an insulating support thick than 0.5mm. The VCP 0.5m by 0.5m in size & HCP were constructed from the same material type & thinness as that of the GRP, and connected to the GRP via a 470kΩ resistor at each end.
The distance between EUT and any of the other metallic surface excepted the GRP, HCP & VCP was greater than 1m.
The EUT was arranged and connected according to its functional requirements.

Direct static electricity discharges was applied only to those points and surface which are accessible to personnel during normal usage.

2. Test result

Location of Discharge	Type of Discharge	Level(kV)	Polarity	Number of Discharge	Result
Remote Receiver	Air	8.0	±	10	A
Display window	Air	8.0	±	10	A
Manual key	Air	8.0	±	10	A
Touchable screw	Contact	4.0	±	10	A
Remote Controller	Air	8.0	±	10	A
	HCP	4.0	±	10	A
	VCP	4.0	±	10	A
Remark: The Air discharge could not occur and the EUT worked normally during the test, no degradation of function occurred.					

Air -Air Discharge
Contact -Contact Discharge
HCP—Horizontal Coupling Plate,
VCP—Vertical Coupling Plate

5.2 Electrical Fast Transient/Burst (EFT)

Date of testing	:	2013.03.08
Temperature	:	26°C
Humidity	:	66%RH
Test procedure	:	EN55014-2: 1997+A1: 2001+A2:2008
Basic Standard	:	IEC 61000-4-4:2004
Repetition Frequency	:	5kHz
Performance Criterion	:	B
Operational mode	:	Cool, High fan
Test result	:	Pass

1.Test Setup

The EUT is placed on an insulating plane, it is 0.1m high for table model and 0.1m high for floor type above the grounded reference plane. EUT is at least 0.5m away from the wall of the EMC laboratory and other metal conductors grounded except the grounded reference plane., and its four borders are at least 0.1m away from the borders of the grounded reference plane. The cable between EUT and CDN is not more than 0.5m.

For signal lines and control lines, the burst signal is coupled by a capacitive coupling clamp.

2. Test result:

Location	Voltage (kV)	Duration (s)	Coupled by	Result
L +N+PE	±1	120	CDN	A
Interconnection line	±0.5	120	Capacitive Coupling Clamp	A
Remark: The EUT worked normally during the test, no degradation of function occurred.				

5.3 Surge

Date of testing	:	2013.03.08
Temperature	:	26°C
Humidity	:	66%RH
Test procedure	:	EN55014-2: 1997+A1: 2001+A2:2008
Basic Standard	:	IEC 61000-4-5:2005
Performance Criterion	:	B
Operational mode	:	Cool, High fan
Test result	:	Pass

1.Test Setup

The cable between EUT and CDN is not more than 1m..
No other special specifications.

2.Test result

Location	Polarity	Phase Angle	Number of test	Pulse Voltage (kV)	Result
L—N	±	0°	5	1	A
	±	90°	5	1	A
	±	180°	5	1	A
	±	270°	5	1	A
L-PE	±	0°	5	2	A
	±	90°	5	2	A
	±	180°	5	2	A
	±	270°	5	2	A
N-PE	±	0°	5	2	A
	±	90°	5	2	A
	±	180°	5	2	A
	±	270°	5	2	A
Remark: The EUT worked normally during the test, no degradation of function occurred.					

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

5.4 Immunity to conducted Disturbances, induced by RF fields

Date of testing	:	2013.03.08
Temperature	:	26°C
Humidity	:	66%RH
Test procedure	:	EN55014-2: 1997+A1: 2001+A2:2008
Basic Standard	:	IEC 61000-4-6:2008
Frequency range	:	150k~230MHz
Modulation	:	80%AM, 1kHz sine-wave
Dwell time/Step size	:	3000ms / 1%
Performance Criterion	:	A
Operational mode	:	Cool, High fan
Test result	:	Pass

1. Test Setup

Frequency Range	Coupling Port	Strength	Coupling Method	Result
0.15MHz~80MHz	AC Mains	3V	CDN	A
80MHz~230MHz	AC Mains	3V	CDN	A
0.15MHz~80MHz	Interconnection wire	1V	Coupling/Decoupling Network	A
80MHz~230MHz	Interconnection wire	1V	Coupling/Decoupling Network	A
Remark: The EUT worked normally during the test, no degradation of function occurred.				

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB

5.5 Voltage Dips and Short interruptions

Date of testing	:	2013.03.08
Temperature	:	26°C
Humidity	:	66%RH
Test procedure	:	EN55014-2: 1997+A1: 2001+A2:2008
Basic Standard	:	IEC 61000-4-11:2004
Performance Criterion	:	C
Operational mode	:	Cool, High fan
Test result	:	Pass

1.Test Setup

No other special specifications.

2. Test result.

Severity Level		Test Level	Duration	Intervals	Phase Angle	Number of Test	Result
Short Interruption 100%		0%U_T	0.5P	3min	0°	3	A
					180°	3	A
Voltage Dips	60%	40%U_T	10P	3min	0°	3	B
					180°	3	B
	30%	70%U_T	25P	3min	0°	3	B
					180°	3	B

Remark:

1, U_T: Nominal Voltage of EUT.

2, During the test of 40%U_T, 70%U_T the EUT stopped, but it could recover the primal status. No degradation of function occurred.

THIS TEST REPORT IS RESPONSIBLE FOR THE SAMPLE TESTED ONLY AND SHOULD NOT BE DUPLICATED IN PART WITHOUT PERMISSION OF THE TEST LAB